

**Pre-bid Questions and Answers For:**

**Hammock Dunes Parkway and Camino Del Mar Intersection Improvements Project**

**Date:** September 20, 2024

1. A clarification was requested regarding the specified base for the pavers proposed at the intersection.

**Response: Architectural pavers within the intersection are to be installed according to FDOT Specifications, Section 526. No additional installation details are necessary as they are covered by the specifications. The design intent is to match the new pavers as closely as possible to the existing ones, so the contractor must submit a material sample to the engineer for approval before ordering.**

2. Is Utility Adjustments part of this contract?

**Response: Utilities shown to be relocated in Utility Adjustment Sheets will be completed by the Utility Agency Owners. Utilities will remain in place throughout construction.**

3. Can you clarify the irrigation and landscaping note in the plans?

**Response: Irrigation systems are present within the work zone, but their exact locations are not specified in the plans. Contractors should include a \$30,000 allowance for irrigation and landscaping.**

4. Who is responsible for the decorative sign at the intersection of Cam Del Mar?

**Response: Proposed DCDD decorative stone guide signs located at Sta. 110+38 Lt. (Hammock Dunes Pkwy.) and Sta. 206+60 (Camino Del Mar) are the responsibility of the contractor. Contractor is to provide the specifications and details, ensuring they match the existing signs. Prior to commencement of any construction related to these signs, approval needs to be obtained from the DCDD. No construction activities for the decorative signs can begin until the required approval is secured and documented by the Engineer.**

5. There seems to be some additional clearing along the right of way of hammock Dunes past Cam Del Mar on the North side of the road not shown in drawings.

**Response: Standard Clearing & Grubbing along Hammock Dunes Parkway from approximately Sta. 110+00 to Sta. 116+25 is as needed for construction of the roadway and drainage improvements as shown plans. Perform layout survey and coordinate with the CEI.**

**Selective Clearing and Grubbing limits delineated in the Roadway Plans (1), (2), and (4) Sheets, includes the removal of all trees except for Oak Trees and Palm Trees that must be protected during construction.**

6. Would it be possible to get a detail for the pavers.

**Response: Existing architectural pavers within the intersection have been discontinued. An architectural paver sample has not been approved by DCDD. The design intent is to match the new pavers as closely as possible to the existing ones, so the contractor must submit a material sample to the engineer for approval before ordering.**

7. The storm pipe is call out as optional material, is HP pipe acceptable?

**Response: Per drainage note number 3 in the Drainage Structures (1) sheet, match proposed pipe materials with existing pipe materials when connecting proposed pipes with existing pipes. All other pipes are to be RCP Class II.**

8. Is there any tree protection on this project, if so can we have locations and a detail.

**Response: Tree protection will be required for oak and palm trees that are to remain within selective clearing and grubbing areas delineated in the plans only. Cost to be included as part of include a \$30,000 allowance for irrigation and landscaping.**

9. The Type F curb in the bid tab is showing 3,115 LF is this correct?

**Response: For pay item no. 0520-1-10, Concrete Curb & Gutter, Type F the correct quantity total is 1,203 LF. A plan revision will be later issued to include this change.**

10. The Type D curb is only showing 11 LF on Hammock Dunes but it is also down Camino Del Mar.

**Response: At modified flume locations, the design intent is to install type D curb at short sections behind DBI's parallel to the roadway to ensure runoff capture within the inlet. For curb section perpendicular to roadway the curb is in transition from a Type F to Type D as per the plans. The cost of the modified flume is to be included in pay item no. 0520-1-10, Concrete Curb & Gutter, Type F.**

11. Is there any specialty landscaping on this project?

**Response: No. Contractor is to include a \$30,000 allowance for irrigation and landscaping.**